

**PROPERTY OWNER PLEASE GIVE TO GENERAL CONTRACTOR**

**Plainfield Building Inspector:**

**David Lersch 603-675-9318  
Cell 603-381-1929  
e-mail: davejosie@juno.com**

**TO GENERAL CONTRACTOR: ALL ELECTRICIANS & PLUMBERS MUST  
BE LICENSED IN THE STATE OF N.H.**

**PROCEDURE FOR SATISFYING BUILDING INSPECTION REQUIREMENTS**

**THE BUILDING INSPECTOR NEEDS AT LEAST 24 HOURS. NOTICE FOR  
ALL INSPECTIONS**

**The following are stages of construction needing inspection for most new buildings,  
additions to existing buildings, or other construction:**

If you have not done so, you are encouraged to contact David Lersch before beginning any construction to review the details of your project.

**1<sup>st</sup> inspection**

After **excavation** and with footing forms in place. **Do not pour concrete before forms are inspected.**

Perimeter drains must go to daylight or equal.

Prior to pouring concrete slab.

If any structural changes to the existing structure are necessary, contact the Building Inspector prior to starting construction to see if an inspection is necessary.

**2<sup>nd</sup> inspection**

When framing is completed prior to interior plumbing and electrical work.

If buried electrical service, after the conduit is placed. Do not bury the conduit until the ditch is inspected.

**3<sup>rd</sup> inspection**

All plumbing and electrical work roughed in.

Do not install insulation or cover walls until inspection has taken place.

**4<sup>th</sup> inspection**

Final inspection of all systems in building requires that all life safety systems are in place and operational. (When all construction is complete)

**Other inspections may be performed as determined by the Building Inspector.**